




HY/2014/07 Central Kowloon Route – Kai Tak West High pressure waterjet cutting system

Speaker: Wong Tsz Chung, David (王子聰)

Senior Project Manager








Major Scope of Works

- Contract No.: HY/2014/07
- Project: Central Kowloon Route Kai Tak West
- Construction Period: Jan 2018 to Jan 2025
- Client: Highways Department
- Resident Engineer: Arup Mott MacDonald Joint Venture
- Contractor: Gammon Construction Limited
- Contract Sum: HK \$6.24Billion





Major Scope of Works

- 1. 50x30m access shaft with noise enclosure at MTK;
- 2. 100m long C&C tunnel at MTK;
- 3. Demolition and re-provisioning of MTK Public Pier;
- 4. 140m long UWT (Stage 1);
- 5. 240m long UWT (Stage 2);
- 6. 60m long C&C tunnel at Kai Tak;
- 7. 130m long depressed road and 200m long underpass at Kai Tak;
- 8. 390m long underground tunnel ventilation adit at Kai Tak;
- 9. Seawall demolition and construction of new landing steps; and
- 10. Barging Point enclosure and conveyor system.

(total tunnel length ~900m)





Major Scope of Works



Clutch pipe pile: dia. 813mm x 25mm thk

UWT stage 1: 461nos. of pipe piles


Construction period: 25 months

Removal period: 51days

UWT stage 2: 497nos. of pipe piles


Construction period: 25 months

Removal period: 58days













Traditional cutting methods



- ☐ Underwater flame cutting by commercial diving
- 1. Locally excavate 2m below seabed
- 2. Diver trims the pipe pile by underwater flame cutting
- Drawbacks:
- Commercial diving is high risk;
- x Lack of specialist divers
- x Low production rates (1 no/day/gang)
- No other marine work is allowed nearby








Alternative Method (Tender Scheme)

Wire cutting method





WIRE SAWING MACHINE

INSTALLED ON TOP OF WIRE SAW OUT
PLATFORM FOR CUTTING CLUTCHED PIPE PILE.



Alternative Method (Tender Scheme)

Wire cutting method

Excavate seabed for trimming

- Marine mud collapse
- Safety risk to diver


Create opening for trimming

- Reduced diving time for underwater hotworks
- Diver still needs to standby


Trim pipe piles by wire


- Difficulty of cutting through the pipe
- Wire breaks and/or jams in the pipe
- Risk of pipe movement whilst the diver(s) are trying to free the jammed wire pipe















Stage 1: Feasibility study and development Hydraulic Driven Disc Cutting (HDDC)

Mockup of HDDC






Trail of HDDC





Stage 1: Feasibility study and development High Pressure Water Jet Cutting (HPWJC)







Hydraulic Driven Disc Cutting

- ✓ Low investment cost
- ✓ Low machinery cost
- x Risk of jamming
- x Production rate not guarantee
- X Large disc consumption

High Pressure Water Jet Cutting

- ✓ No jamming risk
- ✓ Production rate is guarantee
- ✓ Low material consumption
- X High investment cost
- Comparatively high machinery cost



Stage 2: Full scale prototype trial at yard High Pressure Water Jet Cutting (HPWJC) Set up similar to site condition







Stage 2: Full scale prototype trial at yard High Pressure Water Jet Cutting (HPWJC)










Stage 3: High Pressure Water Jet Cutting (HPWJC) on site



Water Tank




Stage 3: High Pressure Water Jet Cutting (HPWJC) on site












Traditional methods VS Waterjet cutting system


	Conventional diving & hot work	HPWJC (self-developed)
Manufacturing	Low-price	Expensive
Anticipated Production Rate	1 pipe/day	3 pipes/day (inc. setup)
Total Duration (958 pipes total)	958 days	320 days
Labour Requirement	Divers ~2880 man-days (team of 3 divers)	Operators ~640 man-days (team of 2)
Safety risk	High risk (Diving works and underwater flame cutting)	Low risk (Remote at control room)
Cost to Implement	\$\$\$\$	\$















Modelling (BIM)



Advanced Construction



Modular Integrated Construction (MiC)



Prefabricated Steel

Building Information Modelling (BIM)

Granted for **KTW Project**

BIM digitalises the construction process. It can minimise clashes and abortive work and reduce the risks of project delivery failure through better co-ordination, hence achieving clearer programme and costs at all project stages.

Advanced Construction Technologies (ACT)

Granted for KTW Project

With the advance in technology, many manual construction operations can be performed by machines and robots under the supervision of skilled and knowledgeable construction personnel.

Modular Integrated Construction (MiC)

Entry for KTW Project submitted

MiC transfers labour-intensive processes and site-bound wet works (such as concreting, screeding, plastering and most building services installations) to off-site manufacturing yards through standardization, thus enhancing productivity, site safety, environmental performance and cost-effectiveness. The use of MiC will shorten construction time, in particular for interior finishes, fixtures and fittings onsite, and allow better quality control.

Prefabricated Steel Rebar (STB)

The use of prefabricated steel rebar can reduce laborious bar-bending work in construction sites, improve productivity and reduce material wastage.



	CITF (jointly implemented by DEVB/CIC)	Examples from other funding/grant
Objectives	Encourage wider adoption of innovative methods and new technologies in the construction industry - to promote productivity, uplifting built quality, improving site safety and enhancing environmental performance	Enhance site safety - to promote the development and implementation of measures to prevent serious accidents on construction sites
Initial seed funding	HK\$1 Billion	~HK\$10 Million
Scope	BIM, ACT, MiC, Prefab Steel Rebar, Manpower Development	Project based
Max. amount for each entry	Matching up to max. 75% of the total cost of approved project sum (e.g. \$2.5M max. for ACT entries)	~HK\$250K average for each successful entry
Quick approval	Quick approval (30 days) if tool/technology is on pre-approved list, non pre-approval items typical approval within 60 days	~ 60 working days to complete approval
Disbursement mode	By way of reimbursement (paid afterwards), in instalments. 1st request can obtain up to 80% of fund amount	Grant to be disbursed after signing of agreement following fund approval (paid before the expense)

Other observation/sharing from our experience with CITF:


- Very effective process due to use of online portal
- During application and vetting, CITF Secretariat is very helpful for assistance, especially for preparation before meeting of the Vetting Sub-Committee
- Corporate fund ceiling imposed and no further approval for new entries
- Temporary works not applicable for MiC however it is a key element of works for delivery of Civil and Geotechnical projects



Thank You Q&A



High Pressure Water Jet Cutting (HPWJC) Set up





The Prototype waterjet cutting on site

Operation Procedure is proof workable and the work duration is approx. 3hrs 30mins / CPP.

Work Sequence	Duration
1. Pre work check of WCD function	approx. 30mins
2. Installation of WCD to CPP	approx. 30mins
3. Operate WCD for CPP cutting	approx. 2hrs 15mins
4. Dismantle of WCD from CPP	approx. 15mins
Total	3hrs 30mins